

ADDENDUM NO. 1
TO
CITY OF AUBURN, MAINE
2024 RECLAMATION PROJECT
March 7, 2024

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on the Bid Form.

Clarifications to the Bid Documents:

The following changes have been made to the Bid Documents:

Question: Do the terminal ends for slipform concrete curb need to be buried?

Answer: No.

Question: What is the budget?

Answer: \$1,500,000.00

Question: How were the quantities calculated for common excavation, common borrow, and gravels?

Answer: Common excavation is for box cut locations for removal of 18" depth. Common borrow is estimated within the locations on the plan. Gravel is based on the box cut (15"D + 3"A) and reclaim(6"A) sections. Driveways receiving A gravel (304.141) to make matches for the new road elevations.

Question: Please clarify how the ditch quantity was calculated.

Answer: The full length of road requires ditching on both sides excluding the curbing.

Question: Is erosion control blanket/seed required in the flow lines of the ditches?

Answer: The City does not anticipate needing erosion control blanket in the flow lines of the ditches. Seeding of the ditch is required.

Question: Where is Item 304.141 being used on the project?

Answer: This item will be used for the driveway paving to match the new road elevation.

Question: Will non spec gravel be allowed in shoulders?

Answer: Yes, with visual inspection prior to placement.

Question: On Sheet C03, what type of pipe is the existing 36" cross culvert proposed for 20LF of replacement?

Answer: The 36" pipe is HDPE. The intent is to remove and replace the last outlet stick of pipe, which would be a maximum of 20'.

Question: How is the geotextile fabric placed under the riprap being paid for?

Answer: This will be incidental to the riprap item.

Question: Where is the pavement removal item being used on the project?

Answer: This is for the removal of pavement within the box cut sections and driveway pavement to match lines.

Question: What geotextile fabric is acceptable for Item 620.54?

Answer: Mirafi HP270 is called out in the supplemental specification, however approved equals are allowed. Mirafi 600X will be an approved equal.

