

ADDENDUM NO. 1
TO
CITY OF AUBURN, MAINE
2021 RECLAMATION PROJECT
January 15, 2021

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on the attached Bid Form – Addendum #1.

Clarifications to the Bid Documents:

The following changes have been made to the Bid Documents:

Question: Is there going to be an item for 6" Underdrain on the Bid Form?

Answer: Yes see the updated Bid Form below for added 900LF of 605.09.

Question: What is the estimate for this project?

Answer: \$950,000.00

Question: Please clarify Item 202.20.

Answer: This item will be used for removing pavement in driveways and intersections to make matches with the proposed elevated roadway.

Question: Can the road be closed?

Answer: The roads can be closed during geotextile and roadway gravel activities with 72 hour notification to the Engineer and an approved detour.

BID FORM – ADDENDUM #1

MDOT ITEM	DESCRIPTION	UNIT	QNTY	UNIT COST	TOTAL COST
201.23	Tree Removal	EA	13		
201.24	Stump Removal	EA	13		
202.20	Remove Bituminous Concrete Surface	SY	350		
202.201	Sawcut Pavement	LF	500		
202.203	Pavement Butt Joints	SY	180		
203.20	Common Excavation	CY	600		
203.24	Common Borrow	CY	3,000		
211.30	Ditch Excavation	LF	11,400		
304.14	Aggregate Base Course- Crushed Type A	TON	12,800		
304.141	Aggregate Base Course- Crushed Type A (Driveways)	TON	450		
307.32	Reclaim Existing Roadway	SY	16,100		
403.208	Hot Mix Asphalt, 12.5mm – Surface	TON	1,400		
403.209	Hot Mix Asphalt, Hand Work	TON	205		
403.213	Hot Mix Asphalt, 12.5mm - Base	TON	1,850		
409.15	Bituminous tack coat, applied	GAL	450		
603.159	12" Culvert HDPE Pipe	LF	450		
603.169	15" Culvert HDPE Pipe	LF	90		
603.179	18" Culvert HDPE Pipe	LF	120		
603.199	24" Culvert HDPE Pipe	LF	140		
605.09	6" HDPE Underdrain Type B	LF	900		
606.10	Adjust Existing Mailbox Post	EA	12		
606.55	Guardrail Type 3 – Single Rail	LF	400		
609.11	Slipform Vertical Curb - Concrete	LF	820		
610.08	Plain Riprap	TON	260		
615.08	Loam, Seed & Mulch	SY	3,400		
620.54	Stabilization/Reinforcement Geotextile	SY	16,500		
627.733	4" Yellow Painted Pavement Marking Line (DYL)	LF	5,910		
652.39	Work Zone Traffic Control	LS	1		
659.1	Mobilization	LS	1		
			TOTAL		

Written total amount is: _____

Company Name: _____

Signed by: _____

Title: _____

Print Name: _____

Address: _____

Tel. # _____ Date: _____

Addendum Acknowledged:

_____ Date _____

_____ Date _____