

ADDENDUM NO. 1
TO
CITY OF AUBURN, MAINE
2018 MPI PROJECT
March 16, 2018

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the Bid Documents. Any verbal discussions or responses are hereby declared null and void.

Clarifications to the Bid Documents:

The following changes have been made to the Bid Documents:

1. Trench paving, patching from milling and raised crosswalks, regardless of pavement type (19.0mm, 12.5mm, 9.5mm), shall be paid for under Item 403.209 Hot Mix Asphalt, Hand Work. 12.5mm will be acceptable for trench paving.
2. Item 304.14 Aggregate Base Course- Crushed Type A shall be used as gravel shoulders on Summer Street. The material shall be crushed ¾" gravel. See attached bid form.
3. Sweeping of roadway surfaces shall be completed by City of Auburn Public Services. Adequate notice shall be given to the project manager for scheduling. Contractor shall provide sweeping during their milling operations. Hand sweeping shall be completed by the contractor.
4. A raised crosswalk is being proposed at Walton School on Lake Auburn Avenue.
5. Work scheduled on Lake Auburn Avenue shall not conflict with Walton School's schedule.
6. Coring the new 6" underdrain into existing manhole shall be considered incidental to Item 605.09.

BID FORM Addendum #1

| MDOT ITEM | DESCRIPTION | UNIT | QNTY | UNIT COST | TOTAL COST |
|-----------|--|------|--------|-----------|------------|
| 202.202 | Remove Pavement Surface | SY | 19,500 | | |
| 202.203 | Pavement Butt Joints | SY | 250 | | |
| 304.14 | Aggregate Base Course- Crushed Type A | CY | 250 | | |
| 403.209 | Hot Mix Asphalt, Hand Work | TON | 200 | | |
| 403.211 | Hot Mix Asphalt, 9.5mm Shim | TON | 1,200 | | |
| 403.213 | Hot Mix Asphalt, 12.5mm Surface | TON | 3,200 | | |
| 409.15 | Bituminous tack coat, applied | GAL | 1,500 | | |
| 604.18 | Adjust Manhole or Catch Basin to Grade | EA | 50 | | |
| 605.09 | 6" Underdrain Type B | LF | 250 | | |
| 608.26 | Curb Ramp Detectable Warning Fields | SF | 300 | | |
| 609.11 | Vertical Curb Type 1 | LF | 100 | | |
| 609.238 | Terminal Curb Type 1- 8 Foot | EA | 40 | | |
| 609.34 | Bituminous Curb | LF | 250 | | |
| 627.733 | 4" White or Yellow Painted Pavement Marking Line | LF | 44,000 | | |
| 627.75 | White or Yellow Pavement and Curb Marking | SF | 2,500 | | |
| 652.361 | Traffic Control | LS | 1 | | |
| 652.381 | Traffic Officers | HR | 50 | \$65.00 | \$3,250.00 |
| 659.10 | Mobilization | LS | 1 | | |
| | Total | | | | |

Written total amount is: _____

Company Name: _____

Signed by: _____

Title: _____

Print Name: _____

Address: _____

Tel. # _____ Fax # _____

Date: _____

Addendum Acknowledged:

_____ Date _____

_____ Date _____

