

ADDENDUM NO. 2
TO
CITY OF AUBURN, MAINE
2017 MPI PROJECT – HAMPSHIRE STREET RECONSTRUCTION
February 17, 2017

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on the attached Bid Form.

Clarifications to the Bid Documents:

The following changes have been made to the Bid Documents:

1. Neighborhood signs – Can we use high density foam board instead of the redwood?
 - a. Answer – Wood is recommended for the signs. Alternative wood products to Redwood may include Western Red Cedar (Straight Grain), Cyprus or approved equal. A shop drawing submittal and approval is required for the signs and sign materials. Other material types can be proposed but will require City approval.

2. Do you have any photos of the cistern near the old Webster school?
 - a. Answer – no photos are available. Exact width and size of cistern are not known. Depth information is provided on the plans.

3. Just had a question on the specifics on the Bike Rack. It's my understanding there is more than one size available and it can either be surface mounted or embedded. Could more detail be provided on this so I can obtain an accurate price?
 - a. Answer – Bike rack shall be RR2H and accommodate 5 bikes. Bike rack shall be surfaced mounted on concrete pad.

4. Per Sheet 3, note 6. We request clarification on how curbing is to be set in concrete. Is curbing to be set on bricks with concrete poured around the base and under the bottom of the curbing or curbing to be set on gravel mounds with concrete pouring around and under the stones.
 - a. Answer – Curbing to be set to final location and grade and then base is backfilled with concrete, as per section 609. Method for setting the curbing is contractor preference.