

ADDENDUM NO. 2  
TO  
CITY OF AUBURN, MAINE  
2019 CHESTNUT STREET CONSTRUCTION PROJECT  
February 15, 2019

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void.

**Clarifications to the Bid Documents:**

The following changes have been made to the Bid Documents:

Question: What is the invert elevation of the intercepted pipe?

Answer: The invert of the 18" HDPE pipe entering the existing catch basin located across from the proposed 6' paved driveway apron is 5'6" below the rim.

Question: Is pavement removal via excavating allowed?

Answer: Yes, the pavement does not need to be milled where full depth of pavement is proposed to be removed.

Question: Will road closures be allowed for this project?

Answer: Road closures can be accepted through an approved traffic control plan.