# OLIVE GARDEN

## 10 SUBARU DRIVE, AUBURN ME JANUARY 31, 2021



LOCUS MAP

NOT TO SCALE

## DRAWING LIST

C100 EXISTING OVERALL SITE PLAN
C101 SITE DEMOLITION PLAN
C102 PROPOSED SITE LAYOUT PLAN
C103 PROPOSED SIGN PLAN
C200 SITE DETAILS
C300 EROSION CONTROL DETAILS
L-1.0 LANDSCAPE PLAN

## OWNER:

FOUR CORNERS PROPERTY TRUST 591 REDWOOD HIGHWAY SUITE 3215 MILL VALLEY, CA 94941

CONSULTANTS:

TRILLIUM ENGINEERING GROUP
189 MAIN STREET
YARMOUTH, ME 04096

ACS ARCHITECTS 101 SHIPYARD WAY, SUITE B NEWPORT BEACH, CA, 92663 CONSULTING ARCHITECT

ACS Architectura
Construction
Services
Inc


101 Shipyard Way

T 714 436-9000

ARCHITECTS PROJECT

CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WOR
DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW
FOR ANY PERSON, UNLESS ACTING
UNDER THE DIRECTION OF A
LICENSED ARCHITECT, TO ALTER
AN ITEM IN ANY WAY





Issue Date: 10-18-21

REVISION

Restaurant #:

OLIVE GARDEN P62DOM-R


> 10 SUBARU DRIVE

AUBURN ME, 04210

Drawing

COVER SHEET

 $^{\circ}$ 



CONSULTING ARCHITECT

ACS Architectural
Construction
Services
Inc

101 Shipyard Way
Suite B
Newport Beach, CA
92663

T 714 436-9000
acs-architects.com
NPB | MKE | ATL

ARCHITECTS PROJECT Job # 1A0014

CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN—
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WORK
DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW
FOR ANY PERSON, UNLESS ACTING
UNDER THE DIRECTION OF A
LICENSED ARCHITECT, TO ALTER
AN ITEM IN ANY WAY.

ERIC DUBE No. 12630 CENSER CALL

AN KITCHEN

Issue Date: 10-18-21

P Date: 10-18-21
REVISION

Restaurant #:

OLIVE GARDEN P62DOM-R

10 SUBARU DRIVE AUBURN


ME, 04210

Drawing

EXISTING

OVERALL SITE
PLAN

C100



CONSULTING ARCHITECT ACS Architectural Construction Services 101 Shipyard Way T 714 436-9000 Suite B acs-architects.com Newport Beach, CA 92663

NPB | MKE | ATL

1A0014

CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN—
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WORK
DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY.



Issue Date: 10-18-21 **REVISION** 

Restaurant #:


OLIVE GARDEN P62DOM-R

> 10 SUBARU DRIVE

ME, 04210

Drawing DEMOLITION

C101



CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN—
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WORK
DO NOT SCALE DRAWINGS IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY. Issue Date: 10-18-21 REVISION Restaurant #: OLIVE GARDEN P62DOM-R 10 SUBARU DRIVE ME, 04210 Drawing PROPOSED SITE LAYOUT PLAN C102

NPB | MKE | ATL


CONSULTING ARCHITECT

1A0014

ACS Architectura Construction Services



## MOUNT AUBURN AVE




	 LEGEND	
EXISTING	DESCRIPTION	PROPOSED
	GRANITE MONUMENT – 3' OFFSET	PROPOSED
O IPF	IRON PIN FOUND/SET	O IPS
OIRF	IRON ROD FOUND	0""
Ç CIRF	CAPED IRON ROD FOUND	
● DHF	DRILL HOLE FOUND	
MON	GRANITE MONUMENT FOUND	
	STREET LINE	
	LOT SETBACKS	
	PROPERTY LINE	
	ABUTTOR LINE	
	"NO CUT" BUFFER	
<u> 1111 1111 1111 1111                 </u>	WETLANDS	
	EDGE OF ROAD/TRAVELLED WAY	
<b>●</b> <sup>TP 69</sup>	SOIL TEST PIT	<b>●</b> <sup>™</sup> 69
— — 101 — —	CONTOUR	101
327x60 x 327.6	SPOT GRADE	327x60 x 327.6
<b>⊚</b> GAS	GAS SHUT-OFF	
Ø <sup>UP</sup>	UTILITY POLE	Ø <sup>UP</sup>
	OVERHEAD ELECTRICAL	—— OE — —
— OE — —	UNDERGOUND ELECTRICAL	
— —UE&T— — [T]	ELECTRICAL TRANSFORMER	— —UE&T— — [T]
	FIRE HYDRANT	
— 8"−W 8" W —	WATER LINE	— 8"-W 8" W —
₩ <sup>WG</sup>	WATER GATE	
— — 12" S— —	SEWER LINE	——12" S— —
S  S  S  MH  S  S  S  S  S  S  S  S  S  S  S  S  S	SEWER MANHOLE	● SMH-1
<b>⊕</b> DMH	DRAINAGE MANHOLE	● DMH-1
<b>■</b> CB	CATCH BASIN	<b>■</b> CB-1
— — UD/SD— — — — UD — —	UNDERDRAIN/STORMDRAIN UNDERDRAIN	— —UD/SD— — — —UD — —
	SILT FENCE	——SF ———
	TEMP. STONE CHECK DAM	$\Diamond$
	GRADING AND FLOW DIRECTION	
	HAY BALES	
	EROSION CONTROL BLANKET	
	STORMWATER BOUNDARY	
$\longrightarrow$	STORMWATER FLOW (Tc)	$\mid \longrightarrow \mid$
	FACE OF LEDGE OUTCROP	
	BIRCH	
(and	MAPLE	
·	Tree line	
	SITE LIGHTING (BAYSIDE FIXTURE)	<b>□-•-</b> □
	STONE WALL	

PROPOSED SIGN PLAN

NPB | MKE | ATL

CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN—
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WORK
DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY.





Issue Date: 10-18-21 REVISION

Restaurant #:


OLIVE GARDEN P62DOM-R


> 10 SUBARU DRIVE

ME, 04210

PROPOSED SIGN

C103






ALL SIGNS SHALL HAVE TYPE III HIGH INTENSITY REFLECTIVE SHEETING ON 0.08" ALUMINUM. REFERENCE "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF ROADS AND BRIDGES ON FEDERAL HIGHWAY PROJECTS", FP-96, SECTION 718.01 AND "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" 2009 EDITION


TYPICAL ADA SIGNAGE DETAIL


SCALE: NTS

SCALE: NTS

SCALE: NTS







1. COMPACT GRAVEL SUBBASE, BASE COURSE TO 95% OF MAXIMUM DENSITY USING HEAVY ROLLER COMPACTION. 2. CONTRACTOR SHALL SET GRADE STAKES MARKING SUBBASE AND FINISH GRADE ELEVATIONS FOR CONSTRUCTION

SCALE: 1

## TYPICAL PARKING LOT SECTION

NOTES: 1. CURB RAMP LENGTHS ARE BASED ON SIX (6) INCH CURB REVEAL HEIGHT AND NO RUNNING SLOPE. RAMP LENGTHS SHALL BE ADJUSTED AS NECESSARY TO ACCOMMODATE VARYING CURB REVEAL HEIGHTS AND TO MATCH RUNNING SLOPES OF

ADJACENT ROADWAY AND SIDEWALK SLOPES TO MAINTAIN A RAMP THAT DOES NOT EXCEED THE MAXIMUM RAMP SLOPE OF

TYPICAL GRANITE CURB INSTALLATION DETAILS

2. DETECTABLE WARNINGS SHALL CONSIST OF RAISED TRUNCATED DOMES AND SHALL HAVE A BASE DIAMETER OF 0.9 INCHES (23 mm) MINIMUM AND 1.4 INCHES (36 mm) MAXIMUM; A TOP DIAMETER OF 50 PERCENT OF THE BASE DIAMETER MINIMUM TO 65 PERCENT OF THE BASE DIAMETER MAXIMUM AND A HEIGHT OF 0.2 INCHES (5.1 mm), A CENTER-TO-CENTER SPACING OF 1.6 INCHES (41mm) MINIMUM AND 2.4 INCHES (61mm) MAXIMUM; AND A BASE-TO-BASE SPACING OF 0.65 INCHES (17mm) MINIMUM, MEASURED BETWEEN THE MOST ADJACENT DOMES ON A SQUARE GRID.

3. DETECTABLE WARNINGS SHALL CONTRAST VISUALLY WITH ADJOINING SURFACES, EITHER LIGHT-ON-DARK, OR DARK-ON-LIGHT. THE MATERIAL USED TO PROVIDE CONTRAST SHALL BE AN INTEGRAL PART OF THE WALKING SURFACE. DETECTABLE WARNINGS USED ON INTERIOR SURFACES SHALL DIFFER FROM ADJOINING WALKING SURFACES IN RESILIENCY OR SOUND-ON-CANE CONTACT.


4. ALL ACCESSIBLE ROUTE SIDEWALKS INTERSECTING ROADWAYS, DRIVEWAYS, OR OTHER VEHICULAR CROSSINGS REQUIRE DETECTABLE WARNINGS. DETECTABLE WARNING ZONES SHALL BE INSTALLED SIX (6) INCHES (OR THE HORIZONTAL THICKNESS OF THE ADJACENT CURB) FROM THE FLOW LINE OF THE CURB, EXTEND INTO THE SIDEWALK FOR A 24" DEPTH, AND COVER THE COMPLETE WIDTH OF THE SIDEWALK OR RAMP AREA. DETECTABLE WARNING ZONES SHALL CONFORM TO THE SLOPE REQUIREMENTS OF THE RAMP, LANDING, OR ACCESSIBLE ROUTE AS DEFINED IN THE SPECIFIED DETAIL. DETECTABLE WARNINGS SHALL NOT BE INSTALLED IN FLARED SIDES, IF THE RAMP INCLUDES FLARED SIDES.


5. ALL LANDING AREAS SHALL BE 4 FEET WIDE BY 4 FEET LONG (MINIMUM DIMENSIONS). THE SLOPE OF THE LANDING AREA SHALL NOT EXCEED A 1:48 IN ANY DIRECTION.

6. ALL ACCESSIBLE ROUTE SLOPES ADJOINING THE LANDING AREA, EXCLUDING THE CURB RAMP, SHALL NOT EXCEED A SLOPE OF 1:20 UNLESS OTHERWISE NOTED.

\_\_ MATCH SIDEWALK SLOPE PER PLAN LANDING (SEE NOTE 5) MATCH SIDEWALK SLOPE PER PLAN

TYPICAL SEWER CONNECTION DETAILS






SCALE: NTS

TYPICAL SIDEWALK RAMP DETAILS


TYPICAL WATER SERVICE DETAIL

SCALE: NTS



GENERAL NOTES

1. CONTRACTOR SHALL CONFIRM ALL PIPE SIZES WITH THE CITY WATER DISTRICT. 2. WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE CITY WATER DISTRICT STANDARDS. 3. CONTRACTOR SHALL STUB NEW SERVICES AT THE EDGE OF THE R.O.W. IN THE MIDDLE OF EACH LOT, UNLESS OTHERWISE NOTED ON THE PLAN/PROFILES. 4. FINAL LOCATION OF ALL BLOW OFF VALVES, SHUT OFF VALVES, STREET BOXES AND HYDRANT VALVES SHALL BE IN ACCORDANCE WITH THE CITY WATER DISTRICT.



- FLARED SIDES

**GENERAL NOTES:** 1. LIQUID CAPACITY: 1,500 GAL. TANK DESIGNED FOR H-20 TRAFFIC WHEEL LOAD w/ DRY SOIL CONDITIONS (WATER TABLE BELOW TANK). EARTH COVER OVER TANK NOT TO EXCEED 6 SUITABLE NATIVE OR SUB-BASE SHALL BE PREPARED TO HANDLE ANTICIPATED LOADS. THE EXCAVATION SHALL BE BEDDED w/ SUITABLE GRANULAR MATERIAL AND SHALL BE COMPACTED TO 90% MAX. DRY DENSITY, OR TO REQUIREMENTS OF THE PROJECT GEOTECHNICAL ENGINEER.

— 4" PVC INLET & OUTLET, PIPE AND FITTINGS STANDARD — LIQUID LEVEL

TYPICAL GREASE TRAP DETAIL


SCALE: NTS

ACS Architectura Construction NPB | MKE | ATL

ARCHITECTS PROJECT 1A0014

THE JOB SITE AND NOTIFY THE ARCHITECTS OF ANY DIMEN-SIONAL ERRORS, OMISSIONS OR DISCREPANCIES BEFORE BEGIN-NING OR FABRICATING ANY WORK DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY.



Issue Date: 10-18-21

REVISION

Restaurant #:

OLIVE GARDEN P62DOM-R

10 SUBARU

DRIVE

ME, 04210 Drawing

SITE DETAILS

## **EROSION AND SEDIMENTATION NOTES**

1. THIS PLAN HAS BEEN DEVELOPED TO PROVIDE A STRATEGY FOR DEALING WITH SOIL EROSION AND SEDIMENTATION DURING AND AFTER PROJECT CONSTRUCTION. THIS PLAN IS BASED ON THE STANDARD AND SPECIFICATIONS FOR EROSION PREVENTION AS CONTAINED IN THE MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: "MAINE EROSION AND SEDIMENT CONTROL BMPs" PUBLISHED BY THE MAINE DEP, LATEST EDITION.

#### GENERAL EROSION AND SEDIMENTATION CONTROL PRACTICES

- 1. EROSION/SEDIMENT CONTROL DEVICES
- THE FOLLOWING EROSION SEDIMENTATION CONTROL DEVICES ARE PROPOSED FOR CONSTRUCTION ON THIS PROJECT. INSTALL THESE DEVICES AS INDICATED ON THE PLANS. 1.1 SILT FENCE: SILT FENCE WILL BE INSTALLED ALONG THE DOWN GRADING EDGES OF DISTURBED AREAS TO TRAP RUNOFF BORNE SEDIMENTS UNTIL THE SITE IS STABILIZED. IN AREAS WHERE STORMWATER DISCHARGES THE SILT FENCE WILL BE REINFORCED WITH HAY BALES TO HELP MAINTAIN
- 1.2 HAY BALES TO BE PLACED IN LOW FLOW DRAINAGE SWALES AND PATHS TO TRAP SEDIMENTS AND REDUCE RUNOFF VELOCITIES. DO NOT PLACE HAY BALES IN FLOWING WATER OR STREAMS. 1.3 RIPRAP: PROVIDE RIPRAP IN AREAS WHERE CULVERTS DISCHARGE OR AS SHOWN ON THE PLANS. 1.4 LOAM. SEED. & MULCH: ALL DISTURBED AREAS. WHICH ARE NOT OTHERWISE TREATED. SHALL

THE INTEGRITY OF THE SILT FENCE AND TO PROVIDE ADDITIONAL TREATMENT.

- RECEIVE PERMANENT SEEDING AND MULCH TO STABILIZE THE DISTURBED AREAS. THE DISTURBED AREAS WILL BE REVEGETATED WITHIN 5 DAYS OF FINAL GRADING. SEEDING REQUIREMENTS ARE PROVIDED AT THE END OF THIS SPECIFICATION. 1.5 STRAW AND HAY MULCH: USED TO COVER DENUDED AREAS UNTIL PERMANENT SEED OR EROSION CONTROL MEASURES ARE IN PLACE. MULCH BY ITSELF CAN BE USED ON SLOPES LESS THAN 15% IN
- SUMMER AND 8% IN WINTER. ALL OTHER SLOPES MUST BE COVERED WITH JUTE MESH OVER MULCH, OR CURLEX II OR EXCELSIOR MAY BE USED IN PLACE OF JUTE MESH AND MULCH OVER LOAM AND SEED. 1.6 MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%. VEGETATED DRAINAGE SWALES SHALL BE LINED WITH EXCELSIOR OR CURLEX.
- 2. TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES PROVIDE THE FOLLOWING TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION OF THE DEVELOPMENT:
- 2.1 SILTATION FENCE ALONG THE DOWNGRADIENT SIDE OF THE PARKING AREAS AND OF ALL FILL SECTIONS. THE SILTATION FENCE WILL REMAIN IN PLACE UNTIL THE SITE IS 85% REVEGETATED.
- 2.2 HAY BALES PLACED AT KEY LOCATIONS TO SUPPLEMENT THE SILT FENCE. 2.3 PROTECT TEMPORARY STOCKPILES OF STUMPS, GRUBBINGS, OR COMMON EXCAVATION AS FOLLOWS:
- A. SOIL STOCKPILE SIDE SLOPES SHALL NOT EXCEED 2:1. B. AVOID PLACING TEMPORARY STOCKPILES IN AREAS WITH SLOPES OVER 10 PERCENT, OR NEAR DRAINAGE SWALES. SEE ITEM 3 IN CONSTRUCTION PHASE NOTES BELOW. C. STABILIZE STOCKPILES WITHIN 15 DAYS BY TEMPORARILY SEEDING WITH A HYDROSEED
- METHOD CONTAINING AN EMULSIFIED MULCH TACKIFIER OR BY COVERING THE STOCKPILE WITH MULCH. D. SURROUND STOCKPILE SOIL WITH SILTATION FENCE AT BASE OF PILE.
- 2.4 ALL DENUDED AREAS WHICH HAVE BEEN ROUGH GRADED AND ARE NOT LOCATED WITHIN THE BUILDING PAD, OR PARKING AND DRIVEWAY SUBBASE AREA SHALL RECEIVE MULCH WITHIN 30 DAYS OF INITIAL DISTURBANCE OF SOIL OR WITHIN 15 DAYS AFTER COMPLETING THE ROUGH GRADING OPERATIONS. IN THE EVENT THE CONTRACTOR COMPLETES FINAL GRADING AND INSTALLATION OF LOAM AND SOD WITHIN THE TIME PERIODS PRESENTED ABOVE, INSTALLATION OF MULCH AND NETTING, WHERE APPLICABLE,
- 2.5 IF WORK IS CONDUCTED BETWEEN OCTOBER 15 AND APRIL 15, ALL DENUDED AREAS ARE TO BE COVERED WITH HAY MULCH, APPLIED AT TWICE THE NORMAL APPLICATION RATE, AND ANCHORED WITH FABRIC NETTING. THE PERIOD BETWEEN FINAL GRADING AND MULCHING SHALL BE REDUCED TO A 15
- 2.6 TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE THE SITE HAS BEEN STABILIZED OR IN AREAS WHERE PERMANENT EROSION CONTROL MEASURES HAVE BEEN INSTALLED. 3. PERMANENT EROSION CONTROL MEASURES
- THE FOLLOWING PERMANENT CONTROL MEASURES ARE REQUIRED BY THIS EROSION/SEDIMENTATION 3.1 ALL AREAS DISTURBED DURING CONSTRUCTION, BUT NOT SUBJECT TO OTHER RESTORATION
- SHALL BE STOCKPILED AND REUSED FOR FINAL RESTORATION WHEN IT IS OF SUFFICIENT QUALITY. 3.2 SLOPES GREATER THAN 2:1 WILL RECEIVE RIPRAP.

(PAVING, RIPRAP, ETC.), WILL BE LOAMED, LIMED, FERTILIZED AND SEEDED. NATIVE TOPSOIL

## **CONSTRUCTION PHASE**

SPECIFIED) AT INLETS AND OUTLETS.

THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION DURING CONSTRUCTION OF

1. ONLY THOSE AREAS UNDER ACTIVE CONSTRUCTION WILL BE CLEARED AND LEFT IN AN UNTREATED OR UNVEGETATED CONDITION. IF FINAL GRADING, LOAMING AND SEEDING WILL NOT OCCUR WITHIN 15 DAYS, SEE ITEM NO. 4.

2. PRIOR TO THE START OF CONSTRUCTION IN A SPECIFIC AREA, SILT FENCING AND/OR HAY BALES

- WILL BE INSTALLED AT THE TOE OF SLOPE AND IN AREAS AS LOCATED ON THE PLANS TO PROTECT AGAINST ANY CONSTRUCTION RELATED EROSION. IMMEDIATELY FOLLOWING CONSTRUCTION OF CULVERTS AND SWALES, RIP RAP APRONS SHALL BE INSTALLED, AS SHOWN ON THE PLANS. 3. TOPSOIL WILL BE STOCKPILED WHEN NECESSARY IN AREAS WHICH HAVE MINIMUM POTENTIAL FOR EROSION AND WILL BE KEPT AS FAR AS POSSIBLE FROM THE EXISTING DRAINAGE COURSE. NO STOCKPILE SHALL BE CLOSER THEN 100' OF A RESOURCE INCLUDING, BUT NOT LIMITED TO, WETLANDS, STREAMS, AND OPEN WATER BODIES. ALL STOCKPILES SHALL HAVE A SILTATION FENCE BELOW THEM
- REGARDLESS OF TIME OF PRESENCE. ALL STOCKPILES EXPECTED TO REMAIN LONGER THAN 15 DAYS A. TREATED WITH ANCHORED MULCH (WITHIN 5 DAYS OF THE LAST DEPOSIT OF STOCKPILED SOIL). B. SEEDED WITH CONSERVATION MIX AND MULCHED IMMEDIATELY. C. INSTALL SILT FENCE AROUND STOCKPILE AT BASE OF PILE.
- STOCKPILES TO HAVE SILT FENCE INSTALLED AT TIME OF ESTABLISHMENT AT BASE OF PILE. 4. ALL DISTURBED AREAS EXPECTED TO REMAIN LONGER THAN 30 DAYS SHALL BE EITHER: A. TREATED WITH ANCHORED MULCH IMMEDIATELY, OR
- B. SEEDED WITH CONSERVATION MIX OF ANNUAL RYE GRASS (0.9 LBS/1000 SQ. FT) AND MULCHED IMMEDIATELY. 5. ALL GRADING WILL BE HELD TO A MAXIMUM 2:1 SLOPE WHERE PRACTICAL. ALL SLOPES WILL
- BE STABILIZED WITH PERMANENT SEEDING, OR WITH STONE, WITHIN 5 DAYS AFTER FINAL GRADING IS COMPLETE. (SEE POST-CONSTRUCTION REVEGETATION FOR SEEDING SPECIFICATION.) 6. ALL CULVERTS WILL BE PROTECTED WITH STONE RIPRAP (D50 = 6" UNLESS OTHERWISE

#### POST-CONSTRUCTION REVEGETATION

- THE FOLLOWING GENERAL PRACTICES WILL BE USED TO PREVENT EROSION AS SOON AS AN AREA IS READY TO UNDERGO FINAL GRADING.
- 1. A MINIMUM OF 4" OF LOAM WILL BE SPREAD OVER DISTURBED AREAS AND GRADED TO A UNIFORM DEPTH AND NATURAL APPEARANCE, OR STONE WILL BE PLACED ON SLOPES TO STABILIZE SURFACES. 2. IF FINAL GRADING IS REACHED DURING THE NORMAL GROWING SEASON (4/15 TO 9/15), PERMANENT SEEDING WILL BE DONE AS SPECIFIED BELOW. PRIOR TO SEEDING, LIMESTONE SHALL BE APPLIED AT A RATE OF 138 LBS/1000 SQ. FT. AND 10: 20: 20 FERTILIZER AT A RATE OF 18.4 LBS/1000 SQ.FT WILL BE APPLIED. BROADCAST SEEDING AT THE FOLLOWING RATES:

#### KENTUCKY BLUEGRASS 0.46 LBS/1000 SF. CREEPING RED FESCUE 0.46 LBS/1000 SF.

TALL FESCUE 0.46 LBS/1000 SF. PERENNIAL RYE GRASS 0.11 LB/1000 SF. 3. AN AREA SHALL BE MULCHED IMMEDIATELY AFTER IS HAS BEEN SEEDED. MULCHING SHALL CONSIST OF HAY MULCH, HYDRO-MULCH, JUTE NET OVER MULCH, PRE-MANUFACTURED EROSION MATS OR ANY SUITABLE SUBSTITUTE DEEMED ACCEPTABLE BY THE DESIGNER.

RED TOP 0.05 LBS/1000 SF.

- A. HAY MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. HAY MULCH SHALL BE SECURED BY EITHER: (NOTE: SOIL SHALL NOT BE VISIBLE) I. BEING DRIVEN OVER BY TRACKED CONSTRUCTION EQUIPMENT ON GRADES OF 5% AND LESS. II. BLANKETED BY TACKED PHOTODEGRADABLE/BIODEGRADABLE NETTING, OR WITH SPRAY, ON
- GRADES GREATER THAN 5%. III. SEE NOTE 6, GENERAL NOTES, AND NOTE 8, WINTER CONSTRUCTION. B. HYDRO-MULCH SHALL CONSIST OF A MIXTURE OF EITHER ASPHALT, WOOD FIBER OR PAPER FIBER AND WATER SPRAYED OVER A SEEDED AREA. HYDRO-MULCH SHALL NOT BE USED BETWEEN 9/15 AND 4/15.
- 15 AND APRIL 15. SHOULD SEEDING BE NECESSARY BETWEEN SEPTEMBER 15 AND APRIL 15 THE FOLLOWING PROCEDURE SHALL BE FOLLOWED. ALSO REFER TO NOTE 9 OF WINTER CONSTRUCTION. A. ONLY UNFROZEN LOAM SHALL BE USED.

B. LOAMING, SEEDING AND MULCHING WILL NOT BE DONE OVER SNOW OR ICE COVER. IF SNOW

4. CONSTRUCTION SHALL BE PLANNED TO ELIMINATE THE NEED FOR SEEDING BETWEEN SEPTEMBER

- EXISTS, IT MUST BE REMOVED PRIOR TO PLACEMENT OF SEED. C. WHERE PERMANENT SEEDING IS NECESSARY, ANNUAL WINTER RYE (1.2 LBS/1000 SQ.FT) SHALL BE ADDED TO THE PREVIOUSLY NOTED AREAS.
- D. WHERE TEMPORARY SEEDING IS REQUIRED, ANNUAL WINTER RYE (2.6 LBS/1000 SQ. FT.) SHALL BE SOWN INSTEAD OF THE PREVIOUSLY NOTED SEEDING RATE.
- E. FERTILIZING, SEEDING AND MULCHING SHALL BE APPLIED TO LOAM THE DAY THE LOAM IS SPREAD BY MACHINERY.
- F. ALTERNATIVE HAY MULCH SHALL BE SECURED WITH PHOTODEGRADABLE /BIODEGRADABLE NETTING. TRACKING BY MACHINERY ALONE WILL NOT SUFFICE.
- . FOLLOWING FINAL SEEDING, THE SITE WILL BE INSPECTED EVERY 30 DAYS UNTIL 85% COVER HAS BEEN ESTABLISHED. RESEEDING WILL BE CARRIED OUT BY THE CONTRACTOR WITHIN 10 DAYS OF NOTIFICATION BY THE ENGINEER THAT THE EXISTING CATCH IS INADEQUATE.

## MONITORING SCHEDULE

UNDERGOING FINAL GRADING.

- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING, MONITORING, MAINTAINING, REPAIRING, REPLACING AND REMOVING ALL OF THE EROSION AND SEDIMENTATION CONTROLS OR APPOINTING A QUALIFIED SUBCONTRACTOR TO DO SO. MAINTENANCE MEASURES WILL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE. AFTER EACH RAINFALL, A VISUAL INSPECTION WILL BE MADE OF ALL EROSION AND SEDIMENTATION CONTROLS AS FOLLOWS: 1. HAY BALE BARRIERS, SILT FENCE, AND STONE CHECK DAMS SHALL BE INSPECTED AND REPAIRED
- ONCE A WEEK OR IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL. SEDIMENT TRAPPED BEHIND THESE BARRIERS SHALL BE EXCAVATED WHEN IT REACHES A DEPTH OF 6" AND REDISTRIBUTED TO AREAS UNDERGOING FINAL GRADING. SHOULD THE HAY BALE BARRIERS PROVE TO BE INEFFECTIVE, THE CONTRACTOR SHALL INSTALL SILT FENCE BEHIND THE HAY BALES VISUALLY INSPECT RIPRAP ONCE A WEEK OR AFTER EACH SIGNIFICANT RAINFALL AND REPAIR AS NEEDED. REMOVE SEDIMENT TRAPPED BEHIND THESE DEVICES ONCE IT ATTAINS A DEPTH EQUAL TO 1/2 THE HEIGHT OF THE DAM OR RISER. DISTRIBUTE REMOVED SEDIMENT OFF-SITE OR TO AN AREA
- REVEGETATION OF DISTURBED AREAS WITHIN 25' OF DRAINAGE-COURSE/STREAM WILL BE SEEDED WITH THE "MEADOW AREA MIX" AND INSPECTED ON A WEEKLY BASIS OR AFTER EACH SIGNIFICANT RAINFALL AND RESEEDED AS NEEDED. EXPOSED AREAS WILL BE RESEEDED AS NEEDED UNTIL THE AREA HAS OBTAINED 100% GROWTH RATE. PROVIDE PERMANENT RIPRAP FOR SLOPES IN EXCESS OF 3:1 AND WITHIN 25' OF DRAINAGE COURSE.

#### EROSION CONTROL DURING WINTER CONSTRUCTION


- 1. WINTER CONSTRUCTION PERIOD: NOVEMBER 1 THROUGH APRIL 15. WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SUCH THAT NO MORE THAN 1 ACRE OF
- THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME. 3. EXPOSED AREA SHALL BE LIMITED TO THOSE AREAS TO BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. AT THE END OF EACH WORK WEEK NO AREAS MAY BE LEFT UNSTABILIZED OVER THE WEEKEND. 4. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE
- EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, SUCH THAT NO LARGER AREA OF THE SITE IS WITHOUT EROSION CONTROL PROTECTION AS LISTED IN ITEM 2 ABOVE. 5. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1000 S.F. (WITH OR WITHOUT SEEDING) OR DORMANT SEEDED, MULCHED AND ANCHORED SUCH THAT SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH. NOTE: AN AREA IS ALSO CONSIDERED STABLE IF SODDED, COVERED WITH
- GRAVEL (PARKING LOTS) OR STRUCTURAL SAND. BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES THE SLOPES SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1 AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. IF CONSTRUCTION CONTINUES DURING FREEZING WEATHER. ALL EXPOSED AREAS SHALL BE CONTINUOUSLY GRADED BEFORE FREEZING AND THE SURFACE TEMPORARILY PROTECTED FROM EROSION BY THE APPLICATION OF MULCH. SLOPES SHALL NOT BE LEFT UNEXPOSED OVER THE WINTER OR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS TREATED IN THE ABOVE MANNER. UNTIL SUCH TIME AS WEATHER CONDITIONS ALLOW, DITCHES TO BE FINISHED WITH THE PERMANENT SURFACE TREATMENT, EROSION SHALL BE CONTROLLED BY THE INSTALLATION OF BALES OF HAY, SILT FENCE OR STONE CHECK DAMS IN ACCORDANCE WITH THE STANDARD DETAILS SHOWN ON THE DESIGN DRAWINGS. NOTE: DORMANT SEEDING SHOULD NOT BE ATTEMPTED UNLESS SOIL TEMPERATURE REMAINS BELOW 50 DEGREES AND DAY TIME TEMPERATURES REMAIN
- 7. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 8%. VEGETATED DRAINAGE SWALES SHALL BE LINED WITH EXCELSIOR OR CURLEX.
- 8. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH SLOPES GREATER THAN 15%. AFTER OCTOBER 1 THE SAME APPLIES FOR ALL SLOPES GREATER THAN 8%.
- 9. BETWEEN THE DATES OF OCTOBER 15 TO NOVEMBER 1, WINTER RYE IS RECOMMENDED FOR STABILIZATION. AFTER NOVEMBER 1, WINTER RYE IS NOT EFFECTIVE. AROUND NOVEMBER 15 OR LATER, ONCE TEMPERATURES OF THE AIR AND SOIL PERMIT, DORMANT SEEDING IS EFFECTIVE.
- 10. IN THE EVENT OF SNOWFALL (FRESH OR CUMULATIVE) GREATER THAN 1 INCH DURING WINTER CONSTRUCTION PERIOD ALL SNOW SHALL BE REMOVED FROM THE AREAS OF SEEDING AND MULCHING PRIOR TO PLACEMENT.

### SITE INSPECTION AND MAINTENANCE

- 1. WEEKLY INSPECTIONS, AS WELL AS ROUTINE INSPECTIONS FOLLOWING RAIN FALLS, SHALL BE CONDUCTED BY THE GENERAL CONTRACTOR OF ALL TEMPORARY AND PERMANENT EROSION CONTROL DEVICES UNTIL FINAL ACCEPTANCE OF THE PROJECT (85% GRASS CATCH). NECESSARY REPAIRS SHALL BE MADE TO CORRECT UNDERMINING OR DETERIORATION. FINAL ACCEPTANCE SHALL INCLUDE A SITE INSPECTION TO VERIFY THE STABILITY OF ALL DISTURBED AREAS AND SLOPES. UNTIL FINAL INSPECTION, ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL IMMEDIATELY BE CLEANED, AND REPAIRED BY THE GENERAL CONTRACTOR AS REQUIRED. DISPOSAL OF ALL TEMPORARY EROSION AND CONTROL DEVICES SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. IT IS RECOMMENDED THAT THE OWNER HIRE THE SERVICES OF THE DESIGN ENGINEER TO PROVIDE COMPLIANCE INSPECTIONS (DURING ACTIVE CONSTRUCTION) RELATIVE TO IMPLEMENTATION OF THE STORMWATER AND EROSION CONTROL PLANS. SUCH INSPECTIONS SHOULD BE LIMITED TO ONCE A WEEK OR AS NECESSARY AND BE REPORTABLE TO THE OWNER, TOWN AND DEP.
- SHORT-TERM SEDIMENTATION MAINTENANCE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CLEAN OUT ALL SWALES AND STRUCTURES PRIOR TO TURNING PROJECT OVER TO THE CITY.

## MAINTENANCE AFTER CONSTRUCTION


- 1. LONG—TERM PROVISIONS FOR PERMANENT MAINTENANCE OF ALL EROSION AND SEDIMENTATION CONTROL FACILITIES AFTER ACCEPTANCE OF THE PROJECT SHALL BE THE RESPONSIBILITY OF THE OWNER OR THEIR DESIGNEE. SUCH RESPONSIBILITIES INCLUDE BUT ARE NOT LIMITED TO THOSE DETAILED AS FOLLOWS:
- A. PARKING LOT SHALL BE MECHANICALLY SWEPT TWICE PER YEAR. THE FIRST SHALL TAKE PLACE IN THE MID WINTER (JANUARY THAW) TO REMOVE ACCUMULATED SANDS FROM WINTER SANDING TO THIS POINT. THE SECOND SWEEPING SHALL TAKE PLACE AFTER WINTER SANDING OPERATIONS TERMINATE BUT PRIOR TO MAY 1.
- B. INSPECTION OF STORMWATER OUTLET STRUCTURE SHOULD BE CONDUCTED TWICE PER YEAR. ACCESS TO THE STRUCTURE IS THROUGH THE TOP. THE OIL/WATER SEPARATOR UNIT SHALL BE PUMPED DOWN AND THE SEDIMENT AND TRASH SHALL BE REMOVED AT THE TIME OF THE INSPECTION. THE REMOVAL OF ALL SEDIMENT AND TRASH WILL HELP MINIMIZE VOLUME LOSS.
- 2. THE OWNER SHALL FILE A YEARLY MAINTENANCE REPORT TO THE CITY DOCUMENTING THE REQUIRED MAINTENANCE FOR THE STORMWATER SYSTEM.



## "SILTSACK" INSTALLATION INSTRUCTION

- 1. REMOVE THE CATCH BASIN GRATE AND PLACE THE SACK INTO THE OPENING. HOLD OUT APPROXIMATELY SIX (6) INCHES OF THE SACK BEYOND THE BASIN FRAME TO ALLOW ACCESS TO THE "SILTSACK" LIFTING STRAPS. REPLACING THE GRATE BACK INSIDE OF ITS FRAME WILL HOLD THE SACK IN PLACE.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING AND MAINTAINING THIS SEDIMENT CONTROL DEVICE. THE SACK IS CONSIDERED FULL AND READY TO EMPTY WHEN THE THE "RESTRAINT CORD" IS NO LONGER VISIBLE.
- 3. THE "SILTSACK" IS REMOVED BY PLACING TWO (2) PIECES IF 1 INCH DIAMETER REBAR THROUGH THE LIFTING LOOPS LOCATED ON EACH SIDE OF THE SACK AND LIFTING WITH AN APPROPRIATE PIECE OF CONSTRUCTION EQUIPMENT. THE LIFTING STRAPS ARE CONNECTED TO THE BOTTOM OF THE SACK AND THE LIFTING ACTION WILL CAUSE THE SACK TO TURN INSIDE OUT, AND EMPTYING THE CONTENTS. THE SACK SHOULD THEN BE CLEANED, RINSED AND RETURNED TO ITS ORIGINAL SHAPE AND PLACED BACK IN THE BASIN.
- 4. THE "SILTSACK" IS REUSABLE, THEREFORE, ONCE THE CONSTRUCTION CYCLE IS COMPLETE, REMOVE THE SACK FROM THE BASIN, CLEAN AND STORE OUT OF DIRECT SUNLIGHT UNTIL ITS NEXT USE.
- 5. THE "SILTSACK" SEDIMENT CONTROL DEVICE IS MANUFACTURED BY: ACF ENVIRONMENTAL





- UNROLL MAT ONTO GROUND IN DIRECTION OF WATER FLOW. MAT SHOULD LIE FLAT. DO NOT STRETCH MAT OVER GROUND. STRETCHING MAY CAUSE MAT TO BRIDGE DEPRESSIONS IN THE SURFACE AND ALLOW EROSION UNDERNEATH. BURY TRANSVERSE TERMINAL ENDS OF MAT TO SECURE AND PREVENT EROSIVE FLOW UNDERNEATH. - SECURE MAT SNUGLY INTO ALL TRANSVERSE CHECK SLOTS.

BACKFILL AND COMPACT TRENCHES AND CHECK SLOTS AFTER STAKING THE MAT IN BOTTOM OF TRENCH.


UPLIFT OF MAT END BY WATER FLOW. IF INSTALLING IN THE DIRECTION OF A CONCENTRATED WATER FLOW, START NEW ROLLS IN A TRANSVERSE DITCH. - OVERLAP ADJACENT EDGES OF MAT BY THREE (3) INCHES (MIN.) AND STAKE. - WOOD STAKES ARE RECOMMENDED FOR PINNING MAT TO THE GROUND SURFACE. STAKES

OVERLAP ROLL ENDS BY THREE (3) FEET (MIN.) WITH UPSLOPE MAT ON TOP TO PREVENT


- SHOULD BE 1" X 3" NOMINAL STOCK CUT IN A TRIANGULAR SHAPE. STAKES SHOULD BE 12" TO 18" LONG, DEPENDING ON SOIL DENSITY. - DRIVE WOODEN STAKES TO WITHIN THREE (3) INCHES OF GROUND
- SURFACE. DO NOT DRIVE FLUSH TO SURFACE. - IN ALL TRANSVERSE TERMINAL TRENCHES AND CHECK SLOTS, STAKE EACH MAT AT ITS CENTER AND OVERLAP EDGES BEFORE BACKFILLING AND COMPACTING.
- STAKE OVERLAPS LONGITUDINALLY AT THREE (3) TO FIVE (5) FOOT INTERVALS. - FOLOW COLORED DOT PATTERNS BY MANUFACTURER

#### REQUIRED ON ALL SLOPES > 8% (WINTER CONSTRUCTION) REQUIRED ON ALL SLOPES > 15% (SUMMER CONSTRUCTION)


EROSION CONTROL BLANKET GENERAL INSTALLATION GUIDELINES ON SLOPES



CONSTRUCTION NOTES: A. BURY THE TOP OF THE NETTING IN A TRENCH 6" OR MORE DEEP B. TAM TRENCH FULL OF SOIL. SECURE WITH ROW OF STAPLES, 12" SPACING, 4" DOWN FROM THE TRENCH C. OVERLAP— BURY UPPER END OF LOWER STRIP AS IN "A" & "B". OVERLAP END OF TOP STRIP 4" AND STAPLE D. CHECK SLOT- FOLD OF NETTING BURIED IN SLIT TRENCH AND TAMPED; DOUBLE ROW OF STAPLES AT 12" SPACING. USE CHECK SLOTS AT 15" SPACING IN DITCHES OR STEEP SLOPES.



EROSION CONTROL BLANKET REQUIRED IN ALL DITCHES > 3% NOTE: GRADING PLAN GOVERNS IN ALL LOCATIONS




NET

∕—BACKFILL

FILTER FABRIC

FLOW



PROVIDE STEEL COUPLER -

EDIMENTATION


₩OOD POST

FROM SITE —

MAY BE USED IN LIEU OF SILT FENCE

**EROSION CONTROL MIX DETAIL** 

CONTROL FABRIC -



SILTATION FENCE INSTALLATION

1. EXCAVATE A 6"x6" TRENCH ALONG THE LINE OF PLACEMENT FOR THE FILTER BARRIER.

**EXISTING** 

GROUND -

- 2. UNROLL A SECTION AT A TIME AND POSITION THE POSTS AGAINST THE BACK (DOWNSTREAM) WALL OF THE TRENCH. 3. DRIVE POSTS INTO THE GROUND UNTIL APPROXIMATELY 2 OF FABRIC IS LYING ON THE TRENCH BOTTOM. JOIN SECTION
- 4. LAY THE TOE-IN FLAP OF FABRIC ONTO THE UNDISTURBED BOTTOM OF THE TRENCH, BACKFILL THE TRENCH AND TAMP THE SOIL. TOE-IN CAN ALSO BE ACCOMPLISHED BY LAYING THE FABRIC FLAP ON UNDISTURBED GROUND AND PILING AND TAMPING FILL AT THE BASE, BUT MUST BE ACCOMPLISHED BY AN INTERCEPTION DITCH.
- 5. BARRIER SHALL BE MIRAFI SILT FENCE OR APPROVED EQUAL.


ONSULTING ARCHITECT ACS Architectura Construction

NPB | MKE | AT

ARCHITECTS PROJECT

JOB SITE AND NOTIFY E ARCHITECTS OF ANY DIMEN-NAL ERRORS, OMISSIONS OF CREPANCIES BEFORE BEGIN-NING OR FABRICATING ANY WORK DO NOT SCALE DRAWINGS

A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY.



sue Date: 10-18-21

REVISION


OLIVE GARDEN P62DOM-R

||Restaurant #:

10 SUBARU

DRIVE ME, 04210

||Drawing



## PLANTING NOTES

- 1. CONTRACTOR SHALL SUPPLY PLANTS IN QUANTITIES SUFFICIENT TO COMPLETE WORK SHOWN ON THE PLAN. ANY DISCREPANCY BETWEEN THE QUANTITIES SHOWN IN THE PLANT SCHEDULE AND THOSE REQUIRED ON THE PLAN SHALL NOT ENTITLE THE CONTRACTOR TO ADDITIONAL RENUMERATION. ANY DESCREPANCIES SHALL BE CLARIFIED BY THE LANDSCAPE ARCHITECT PRIOR TO ORDERING OF ANY PLANT MATERIAL.
- 2. ALL PLANT SUBSTITUTIONS SHALL BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO THE ORDERING OF PLANTS.
- 3. ALL MATERIALS SHALL CONFORM TO SPECIFICATIONS OF THE AMERICAN STANDARDS FOR NURSERY STOCK (LATEST EDITION) AS SET FORTH BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- 4. ALL PLANTS SHALL BEAR THE SAME RELATIONSHIP TO FINISH GRADE AS THE ORIGINAL GRADES BEFORE DIGGING.
- 5. THE LANDSCAPE CONTRACTOR SHALL CONTACT DIG-SAFE (888-DIG-SAFE) PRIOR TO PLANT INSTALLATION TO CONFIRM LOCATION OF ALL UNDERGROUND UTILITIES.
- 6. NO PLANT MATERIAL SHALL BE INSTALLED UNTIL BED PREPARATION, AND FINISH GRADING HAS BEEN COMPLETED IN THE IMMEDIATE AREA.
- 7. BED EDGING SHALL BE 5" BLACK COMMERCIAL ALUMINUM OR STEEL EDGING INSTALLED WITH 12" SPIKES. BEDS WITHIN THE BUILDING PAD AREA SHALL USE STONE MULCH TO MATCH BUILDING VENEER (SEE OLIVE GARDEN LANDSCAPE STARNDARDS & GUIDELINES MANUAL FOR STONE SPECIFICATIONS); PERIPHERAL BEDS SHALL HAVE 3" OF UNIFORMLY DISTRIBUTED HARDWOOD BARK
- 8. ALL PLANTS SHALL BE BALLED AND WRAPPED OR CONTAINER GROWN AS SPECIFIED. ALL ROOT WRAPPING, WIRE CAGES, AND CONTAINER MATERIAL MADE OF SYNTHETICS OR PLASTICS SHALL BE REMOVED AT THE TIME OF PLANTING.
- 9. ALL PLANTS SHALL BE INSTALLED AS PER DETAILS AND THE CONTRACT SPECIFICATIONS. THE LANDSCAPE CONTRACTOR SHALL REFER TO THE CONTRACT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS NOT SHOWN ON THIS PLAN.
- 10. ALL PLANTS SHALL BE WARRANTEED FOR ONE FULL YEAR FROM DATE OF INSTALLATION OR UNTIL FINAL ACCEPTANCE.
- 11. ALL PROPOSED LAWN AND PLANTING AREAS SHALL BE IRRIGATED; CONTRACTOR SHALL COORDINATE LOCATION OF WATER SOURCE AND SYSTEM MECHANICALS WITH THE GENERAL CONTRACTOR. ONCE SYSTEM IS FULLY ACTIVATED, THE IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR 90-DAY MAINTENANCE OF THE ENTIRE SYSTEM.
- 12. ALL LAWN AREAS SHALL BE SOD UNLESS IDENTIFIED FOR SEED BY THE OWNER. IF APPLICABLE, ALL SEEDED AREAS SHALL USE A PERMANENT SEED MIX ('ESTATE MIX' BY ALLEN, STERLING, & LOTHRUP OF FALMOUTH, MAINE).
- 13. ALL PAVED ROADWAYS AND SIDEWALKS SHALL BE KEPT CLEAN AND FREE OF DEBRIS FOR THE DURATION OF THE PROJECT.

#### **GENERAL NOTES**

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND GRADES IN FIELD, AND NOTIFY THE CIVIL ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

2. ALL DIMENSIONS SHOWN ARE TO FACE OF WALLS, BUILDINGS, AND OTHER SITE ELEMENTS

3. LOAM SHALL BE SPREAD ON THE SITE TO A DEPTH OF 6" IN AREAS IDENTIFIED FOR NEW LAWN. PROPOSED PLANTING AREAS SHALL RECEIVE LOAM/COMPOST MIXTURE TO A DEPTH OF 10" MINIMUM.


4. THE FINISHED SITE SHALL BE GRADED SMOOTH TO REMOVE ALL RIDGES, SWALES, MOUNDS AND DEPRESSIONS UNLESS OTHERWISE NOTED ON THE PLANS. THE CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE AWAY FROM THE STRUCTURE ACCORDING TO SPOT GRADES PROVIDED ON THE SITE GRADING AND DRAINAGE PLAN.

5. IMPORTED SOIL SHALL BE FREE OF INVASIVE PLANTS, WEEDS, SEEDS, AND ANY CHEMICALS OR NOXIOUS MATERIALS. CONTRACTOR SHALL SUBMIT SOIL TEST RESULTS TO THE CIVIL ENGINEER FOR APPROVAL PRIOR TO IMPORTING AND SPREADING OF LOAM ON SITE.

## PLANT SCHEDULE

QTY.	SYM.	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
3	AR	ACER RUBRUM 'KARPICK'	KARPICK RED MAPLE	2-2.5" CAL.	B&B
23	ΑZ	AZALEA 'BIXBY'	BIXBY AZALEA	3 GAL.	CONT.
15	CAC	CLETHRA ALNIFOLIA '16 CANDLES'	COMPACT SUMMERSWEET	2 GAL.	CONT.
3	CV	CRATAEGUS VIRIDIS 'WINTER KING'	WINTER KING HAWTHORN	1.75-2" CAL.	B&B
1	FG	FOTHERGILLA GARDENII	DWARF BOTTLEBRUSH BUSH	24-30"	B&B
3	НО	HOSTA 'KROSSA REGAL'	KROSSA REGAL HOSTA	2 GAL.	B&B
3	HS	HELICTOTRICHON SEMPERVIRENS	BLUE OAT GRASS	2 GAL.	B&B
5	НМ	HYDRANGEA MAC. 'TWIST-N-SHOUT'	TWIST-N-SHOUT HYDRANGEA	5 GAL.	CONT.
10	IGC	ILEX GLABRA 'SHAMROCK'	COMPACT INKBERRY	24-30".	CONT.
11	JS	JUNIPERUS SQUAMATA 'BLUE STAR'	BLUE STAR JUNIPER	2 GAL.	CONT.
17	JCB	JUNIPERUS CHINENSIS 'BLUE POINT'	BLUE POINT UPRIGHT JUNIPER	6-7'	В&В
5	MP	MYRICA PENNSYLVANICA	NORTHERN BAYBERRY	30-36"	CONT.
3	MS	MISCANTHUS SINENSIS 'GRACILLIMUS'	MAIDEN GRASS	3 GAL.	CONT.
42	RA	RHUS AROMATICA 'GRO-LOW'	DWARF FRAGRANT SUMAC	2 GAL.	CONT.
4	SA	SALIX PURPUREA 'NANA'	DWARF ARCTIC WILLOW	5 GAL.	CONT.
15	SP	SPIRAEA X BUMALDA 'NEON FLASH'	NEON FLASH SPIREA	5 GAL.	CONT.
3	VB	VIBURNUM CARLESII	KOREANSPICE VIBURNUM	3-4'/HVY.	B+B
2	VSS	VIBURNUM TOMENT. 'SUMMER SNOWFLAKE'	SUMMER SNOWFLAKE VIBURNUM	30-36"/HVY.	B+B

NOTE: ALL SUBSTITUTIONS SHALL BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO ORDERING OF PLANTS



PROPOSED SITE LAYOUT PLAN

FOR PLANNING BOARD REVIEW - NOT FOR CONSTRUCTION

ACS Architecture Construction Services Inc


Suite B acs-architects.c Newport Beach, CA 92663 NPB | MKE |

....

ARCHITECTS PROJECT

CONTRACTOR SHALL VERIFY ALL
CONDITIONS AND DIMENSIONS
AT THE JOB SITE AND NOTIFY
THE ARCHITECTS OF ANY DIMEN—
SIONAL ERRORS, OMISSIONS OR
DISCREPANCIES BEFORE BEGIN—
NING OR FABRICATING ANY WORK
DO NOT SCALE DRAWINGS

IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT, TO ALTER AN ITEM IN ANY WAY.



tudio
chitecture
outh, Maine 04096
cowles-studio.com

cowles studio
landscape architect
189 Main Street Yarmouth, Maine (207.415.4332 www.cowles-studio



Issue Date: 10-18-21
REVISION

 $\triangle$ 

Restaurant #:

OLIVE GARDEN P62DOM-R

> 10 SUBARU DRIVE

AUBURN ME, 04210

||Drawing

LANDSCAPE PLAN

L-1.0

Luminaire Schedule					
Qty			WatAtrarangement	LLF	Description
4	EX1	132	SINGLE	0.900	OSQL-B-22L-40K7-4M-Ux-xx-xx-xxxx-w_OSQ-BLSLF CONFIGURED FROM OSQ-A-xx-4ME-U-57K-
2	EX2	7.5	SINGLE	0.800	AIRIS LARGE - #307930
5	EX3	34	SINGLE	0.530	PWY-EDG-2M-xx-02-E-UL-xx-350
3	EX4	47	SINGLE	0.900	XSPW-B-WM-4ME-6L-40K-UL-xxxx CONFIGURED FROM XSPW-B-WM-4ME-8L-40K-UL-xxxx

Calculation Summary								
Label	Units	Avg	Max	Min	Avg/Min	Max/Min		
SITE	Fc	0.98	16.6	0.0	N.A.	N.A.		
BUILDING PERIMETER AND WEST AREA	Fc	2.78	16.6	0.1	27.80	166.00		
PARKING LOT EAST	Fc	1.39	3.0	0.2	6.95	15.00		
PARKING LOT NORTH	Fc	1.83	3.0	0.5	3.66	6.00		

