BID ADDENDUM NO. 1

City of Auburn, Maine

Sopers Mill Road Culvert Replacement

January 21, 2021

Notice is hereby given that Addendum No. 1 provides further clarification for questions asked by Bidders before and during the Pre-Bid meeting held on January 19, 2021 and includes the registered bidders list. Bidders are instructed to acknowledge receipt of this Addendum by inserting its number and date in the "Acknowledgement of Bid Amendments".

Questions:

- 1. Was there any hydrologic information prepared for the project. Answer: Yes, a copy is included with this addendum.
- 2. Was any geotechnical investigations completed for the project. Answer: No

<u>Drawings</u>: The following new Drawing(s) are herewith added, have an issue date of January 21, 2021 and designated as Addendum No. 1.

New sheets included:

• Sheet G001 – Notes, Abbreviations, Legend and Sheet Index

Attachments: The following items are being provide for bidder reference:

- Registered Plan Holder List
- Pre-Bid Meeting Presentation
- Hydrologic and Hydraulic Analysis Summary

City of Auburn, ME Sopers Mil Road Culvert Replacement Project January 21, 2021 Registered Plan Holders List

Number	Name	Company	Email Address	Phone Number
1	Nick Mathon	J Pratt Construction Inc	nick@jprattinc.com	(207) 577-7914
2	Andrew Ward	Pratt & Sons	andrew@prattandsons.net	(207) 754-3635
3	lan Messier	Crooker Construction	ian@crooker.com	(207) 720-0371
4	Steven Piela	Glidden Excavating & Paving, Inc.	steve@gliddenpaving.com	(207) 856-9990
5	Kolby Martin	Nitram Excavation & General Contractor, Inc.	kolby@nitramexc.com	(207) 692-7746
6	Scott Bois	Gendron & Gendron	scottb@gendroncorp.com	(207) 712-3404
7	Jim DePalma (JD)	Longchamps & Sons, Inc	jd.depalma.ls@gmail.com	(207) 754-5385
8	Adam Lake	CH Stevenson, Inc.	alake@chstevensoninc.com	(207) 685-3600
9	Travis Stearns	C.L.H & Son Inc	travis@clhandson.com	(207) 212-2483
10	Mike Naczas	Construction Summary of NH/Maine/VT, Inc.	mnaczas@constructionsummary.com	(207) 990-1156
11	Larry Morin	St. Laurent & Son Inc	pave@stlaurentandson.com	(207) 784-7944
12	Mitch Elliott	Shaw Brothers Construction, Inc	melliott@shawbrothers.com	(207) 321-1395
13	Craig E Babbidge	Cross Excavation	Craig@crossexcavation.com	(207) 381-7567
14	Kim Suhr	Wyman and Simpson, Inc.	ksuhr@wymanandsimpson.com	(207) 737-4471



Pre-Bid Meeting Sopers Mill Road Culvert Replacement





COMMITMENT & INTEGRITY DRIVE RESULTS



- Introductions & Key Personnel
- Project Overview
- Project Schedule
- Bid Form
- Addendum
- Bid Opening
- Questions





- Owner: City of Auburn
 - City of Engineer: Tony Beaulieu, P.E.
- Engineer: Woodard & Curran
 - Project Manager: Megan McDevitt, P.E.





Overall Goal: Replace deteriorated CMP culvert with precast concrete box culvert

















Project Overview

- Anticipated Sequence of Construction
 - Installation of traffic control measures.
 - Installation of erosion and sedimentation control and water control measures.
 - Demolition of roadway and existing culvert.
 - Installation of precast concrete box culvert with wingwalls.
 - Backfill and reconstruction of roadway.
 - Installation of guardrail.
 - Restoration of disturbed areas.
 - Removal of temporary erosion and sedimentation control, water control and traffic control measures.





- Project Requirements
 - Comply with Army Corps of Engineers General Permit NAE-2020-00667, including:
 - Work Area Isolation and Evacuation of Atlantic Salmon
 - All in-water construction work must be completed between July 15, 2021 and September 30, 2021
 - Provide Traffic Control Plan identifying proposed construction signage and detour prior to pre-construction meeting
 - Precast Concrete Box Culvert to be installed with 2 feet of embedment.
 - Streambanks to be reconstructed within culvert.
 - Clamshell design will be accepted.





- Contract Times
 - Final Completion Date......December 1, 2021
 - Liquidated Damages\$500/Calendar Day
- Start Time
 - Flexible, but in-water work cannot start before July 15, 2021





Bid Form

- **Bid Items Include:**
 - Sopers Mill Road Culvert Replacement- Lump Sum
 - Structural Rock Excavation Drainage & Minor Structures per Cubic Yard
- Bid Security 5 percent of Bid Price





- **Addendum**
- All Addendums *must be* acknowledged on Bid Form
- Send any additional questions in writing to Megan McDevitt, mmcdevitt@woodardcurran.com
 - Deadline to submit written questions: 5:00 pm January 22, 2021





- Thursday, January 28, 2021 at 2:00 pm
- Mail sealed bids to:
 - City of Auburn,
 - Attn: Derek Boulanger, Facilities Manager/Purchasing Agent
 - 60 Court Street
 - Auburn, Maine 04210
- Include "Sopers Mill Culvert Replacement—Bid # 2021-019" on envelope.
- Basis of Award
 - Lowest total base bid price from responsive bidder





Questions?





COMMITMENT & INTEGRITY DRIVE RESULTS

USGS Basin and Stream Flow Statistics & Hydrologic Analysis:

Attribute	Value	Units	Definition	Return Period	Peak Flow Estimate
Drainage Area	inage Area 0.6 square miles Area that drains to crossing		Area that drains to crossing	T (yr)	QT (ft3/s)
Drainage Area	0.0	Square miles		1.01	11
Wetlands	4.66	percent	Percentage of NWI storage	2	36.2
Elev	290	feet	Mean basin elevation	5	57.2
Precip	45.9	inches	Mean annual precipitation	10	72.4
Aquifor	0	percent	Percentage of land surface underlain by aquifers	25	94.5
Aquilei	Aquilei 0 percent rercentage of land surface unde		Percentage of failu surface underfailt by aquifers	50	111
				100	130
Х	402852.64	State Plane Coord.	Basin centroid E/W location	500	176
Y	4873999.98	State Plane Coord.	Basin centroid N/S location	Estimated Bar	nkfull Width = 5.88 ft

Source: USGS StreamStats version 4.3.11, 8/6/2020

Bankfull Statistics Citations

Dudley, R.W., 2004, Hydraulic-Geometry Relations for Rivers in Coastal and Central Maine: U.S. Geological Survey Scientific Investigations Report 2004-5042, 30 p (http://pubs.usgs.gov/sir/2004/5042/pdf/sir2004-5042.pdf)

Peak-Flow Statistics Citations Lombard, P.J., and Hodgkins, G.A., 2015, Peak flow regression equations for small, ungaged streams in Maine— Comparing map-based to field-based variables: U.S. Geological Survey Scientific Investigations Report 2015–5049, 12 p. (http://dx.doi.org/10.3133/sir20155049)

HEC-RAS Hydraulic Analysis Program provides basin flow estimates and culvert discharge results for the following rainfall events at the proposed box culvert design, and indicates that the proposed culvert will pass the expected 100-year storm event:

Discharge	Total	Culvert	Headwater	Inlet	Outlet		Outlet
Name	Discharge (cfs)	Discharge (cfs)	Elevation (ft)	Depth (ft)	Depth (ft)	Flow Type	Velocity (ft/s)
1.01 year	11	11	215.37	1.04	1.26	Subcritical; outlet control	1.18
2 year	36.2	36.2	216.09	1.76	1.96	Subcritical; outlet control	2.26
5 year	57.2	57.2	216.42	2.09	2.28	Subcritical; outlet control	3.01
10 year	72.4	72.4	216.62	2.29	2.46	Subcritical; outlet control	3.48
25 year	94.5	94.5	216.87	2.54	2.69	Subcritical; outlet control	4.11
50 year	111	111	217.03	2.7	2.84	Subcritical; outlet control	4.56
100 year	130	130	217.19	2.86	2.99	Subcritical; outlet control	5.04

100-year storm event water surface profile:



GENERAL NOTES 1. SITE AND TOPOGRAPHIC DATA PROVIDED BY SGC ENGINEERING, LLC OF WESTBROOK, MAINE AS A RESULT OF A SURVEY CONDUCTED FOR THE CITY OF AUBURN IN NOVEMBER 2019. SURVEY CONTROL REFERENCED HORIZONTALLY WITH THE MAINE STATE PLAN COORDINATE SYSTEM, NAD '83, WEST ZONE AND VERTICALLY WITH NAVD '88. 2. THE UTILITY LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND REQUIRE FIELD VERIFICATION BY THE CONTRACTOR PRIOR TO CONSTRUCTION ACTIVITY. NOT ALL EXISTING UTILITIES ARE SHOWN ON PLANS. 3. CONTRACTOR SHALL CLEAN AND/OR FLUSH CULVERT AFTER THE WORK HAS BEEN COMPLETED. FLUSHING SHALL BE INCIDENTAL TO THE CONTRACT. 4. CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITY WITH UTILITY COMPANIES, EMERGENCY SERVICES, AND THE CITY. NOTIFY UTILITY COMPANIES AT LEAST 48 HOURS PRIOR TO WORK ACTIVITY ADJACENT TO THOSE UTILITIES. 5. CONTRACTOR SHALL NOTIFY ALL UTILITIES PRIOR TO COMMENCING WORK, ALLOWING SUFFICIENT TIME TO LOCATE AND MARK THE LOCATION OF BURIED UTILITIES. CONTRACTOR SHALL CONTACT "DIG SAFE", TELEPHONE 888-344-7233, AT LEAST 72 HOURS PRIOR TO EXCAVATION. 6. CONTRACTOR SHALL RESTORE ALL AREA DISTURBED BY CONSTRUCTION ACTITIVIES TO ORIGINAL FINISH (GRAVEL, PAVEMENT, GRASS, ETC.) UNLESS OTHERWISE NOTED ON PLANS. RESTORATION OF LAWNS DAMAGED BY CONTRACTOR OPERATIONS SHALL BE INCIDENTAL TO THE PROJECT. 7. PROPERLY PROTECT AND DO NOT DISTURB PROPERTY IRONS AND MONUMENTS. IF DISTURBED, THE PROPERTY MONUMENT SHALL BE RESET AT THE CONTRACTOR'S EXPENSE, BY A REGISTERED LAND SURVEYOR APPROVED BY THE CITY OR ENGINEER. 8. EXISTING FACILITIES (E.G. GUARDRAILS, TREES, MAILBOXES, POLES, LIGHT POSTS, CATCH BASINS, ETC.) THAT ARE NOT SCHEDULED TO BE REMOVED SHALL BE PROTECTED DURING CONSTRUCTION AND SHALL BE INCIDENTAL TO THE CONTRACT. THE CITY RETAINS RIGHT TO KEEP ANY AND ALL REMOVED FACILITIES. CONTRACTOR TO DISPOSE OF ANY REMOVED FACILITY AT THE REQUEST OF THE CITY OR RESIDENT ENGINEER AT CONTRACTOR'S EXPENSE. 9. DO NOT PARK OR STORE EQUIPMENT ON ADJACENT CITY OR PRIVATELY OWNED LOTS, UNLESS PERMISSION HAS BEEN GRANTED IN WRITING BY CITY OR LAND OWNER. 10. RESTRICT ACCESS TO CONSTRUCTION AREA THROUGH THE USE OF APPROPRIATE SIGNAGE, GATES, BARRIERS, FENCES, ETC. SITE SHALL BE LEFT WITH APPROPRIATE SAFETY MEASURES IN PLACE DURING NON-WORKING HOURS. NO TRENCH SHALL BE LEFT OPEN DURING NON-WORKING HOURS. SITE SAFETY IS THE SOLE RESPONSIBILITY OF CONTRACTOR, DURING BOTH WORKING AND NON-WORKING HOURS. 11. PROVIDE 4 INCHES OF LOAM AND SEED IN ALL LAWN AREAS DISTURBED BY CONTRACTOR'S OPERATIONS. 12. CONTRACTOR SHALL PREPARE A COMPLETE SET OF "RECORD" DRAWINGS THAT REFLECT THE CONSTRUCTED CONDITIONS, INCLUDING PLANIMETRICS, TOPOGRAPHY AND UTILITY INFORMATION. 13. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY CONSTRUCTION PERMITS. PERMIT APPLICATIONS SHALL BE SUBMITTED WITH ADEQUATE TIME SO AS NOT TO DELAY CONSTRUCTION. 14. ALL WORK SHALL BE DONE IN ACCORDANCE WITH MAINE DEPARTMENT OF TRANSPORTATION'S BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENTATION CONTROL, MOST RECENT EDITION. 15. CONTRACTOR TO COORDINATE ROAD CLOSURE WITH THE CITY AND SHALL PROVIDE AND MAINTAIN DETOUR SIGNAGE THROUGHOUT THE DURATION OF CONSTRUCTION. 16. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE DEPARTMENT OF THE ARMY MAINE GENERAL PERMIT NAE-2020-00667, INCLUDING REQUIREMENTS FOR WORK AREA ISOLATION AND EVACUATION OF ATLANTIC SALMON. \sim 17. ALL IN-WATER WORK SHALL BE COMPLETED BETWEEN JULY 15, 2021 AND SEPTEMBER 30, 2021. \sim

Β

D

1

Ę

<u>LEGEND</u>

0	IRON PIPE FOUND	SHEET NO.	SHE
•	CONCRETE BOUND FOUND	GENERAL	
	EXISTING SIGN		~~`
Ū.	UTILITY POLE	G-000	001
-•	GUY ANCHOR	G-001	NO
\bowtie	EXISTING WATER VALVE	CIVIL	
λýς.	EXISTING HYDRANT	C-001	EXI
S	PROPOSED PAVEMENT EXISTING SANITARY SEWER MANHOLE	C-002	SITE
	APPROXIMATE BOREHOLE LOCATION	C-003	CUL
— — —	EXISTING CONTOUR	C-004	GUA
OE	EXISTING OVERHEAD ELECTRIC	C-005	PRO
0 0 0 0 0 0 0 0	EXISTING GUARDRAIL	C-006	PRO
	RIGHT-OF-WAY		
	TOP OF BANK		
v (
	WETLANDS		
CD	PROPOSED COFFERDAM		
• • • • • • • • • • • • • • • • • • •	PROPOSED SEDIMENT BARRIER		
— — — — 519 — — — — —	PROPOSED CONTOUR		
<u> </u>	PROPOSED GUARDRAIL		
	PROPOSED SAWCUT		
	TURBIDITY BARRIER		
	PROPOSED PAVEMENT		
	PROPOSED RIP RAP		

ABBREVIATIONS

BIT.	BITUMINOUS
ONC.	CONCRETE
P.	EDGE OF PAVEMENT
NV.	INVERT
.O.W.	LIMIT OF WORK
ЭНW	OVERHEAD WIRE
I.A.V.D.	NORTH AMERICAN VERTICAL DATUM
ТА	STATION
YP.	TYPICAL

SHEET INDEX

SHEET TITLE

COVER SHEET NOTES, ABBREVIATIONS, LEGEND AND SHEET INDEX

XISTING CONDITIONS PLAN

TTE PREPERATION AND EROSION & SEDIMENT CONTROL PLAN

CULVERT REPLACEMENT PLAN & PROFILE

SUARDRAIL PLAN & DETAILS

PROJECT DETAILS - 1

ROJECT DETAILS - 2

