

ADDENDUM NO. 1
TO
CITY OF AUBURN, MAINE
2016 RECLAMATION PROJECT
December 17, 2015

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the Bid Documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on page 6 of 34 of the Bid Documents.

Clarifications to the Bid Documents:

The following changes have been made to the Bid Documents:

Page 3 of 34, Conditions and Instructions to Bidders Item 12, change the completion date from October 15th, 2016 to July 29th, 2016.

Page 12 of 34, Special Provisions, F-22 Driveways and sidewalks, remove entire section and replace with the following:

“F- 22 Driveways and sidewalks

New sidewalks and matching of existing driveways to new roadway elevations shall be paid for under the following contract items:

203.20 Common Excavation

304.141 Aggregate Base Course- Crushed Type “A” (Driveways)

403.209 Hot Mix Asphalt, Hand Work

Driveway aprons shall receive a minimum of 12” of new gravel with 2” of 12.5mm and 1” of 9.5mm HMA. No separate payment shall be made for sawcutting. Existing pavement edges shall be protected from damage. Construction of aprons shall follow Division 800 Miscellaneous Details, Section 801 Drive Aprons of the Standard Specifications.”

The common excavation quantity has been revised to included driveways. See attached bid form.

Page 17 of 34, Supplemental Specifications, Section 304- Aggregate Base Course, add Pay Item 304.10 Aggregate Base Course Type D, Pay Unit- Ton.

Page 19 of 34, Supplemental Specifications, Section 403- Hot Bituminous Pavement, 403.01 Description, delete “1.5” and replace with “2.5”.

Page 23 of 34, Supplemental Specifications, Section 609- Curb, Section 609.01 Description, delete the following: “Construct Type 3 bituminous curbing. The engineer will determine mold type in the field.” and replace with the following: “Install vertical granite curb.”

Page 23 of 34, Supplemental Specifications, Section 609- Curb, Section 609.10 Basis of Payment, delete “bituminous” and replace with “granite”.

Granite headstones at catchbasins will be paid as Item 609.11 Vertical Granite Curb. Curb inlet stones will not be required.

Item 620.54 Stabilization/Reinforcement Geotextile shall be Mirafi HP270.

The ditching quantity has been revised to 8,750 LF. See attached bid form.

See attached map showing the approximate areas of box cut and reclaim on Pettingill Park Road.

Removal of concrete will be paid under Item 203.20 Common Excavation.

Townsend Brook Road shall remain open to thru traffic and traffic control personnel shall be employed.

The bid opening location has been changed to Council Chambers.

BID FORM- Addendum #1

MDOT ITEM	DESCRIPTION	UNIT	QNTY	UNIT COST	TOTAL COST
202.203	Pavement Butt Joints	SY	200		
203.20	Common Excavation	CY	2,250		
211.30	Ditch Excavation	LF	8,750		
304.10	Aggregate Subbase Course- Crushed Type D	TON	1,500		
304.14	Aggregate Base Course- Crushed Type A	TON	12,500		
304.141	Aggregate Base Course- Crushed Type A (Driveways & Sidewalks)	TON	850		
307.32	Reclaim Existing Roadway	SY	16,000		
403.207	Hot Mix Asphalt, 19.0mm	TON	2,000		
403.208	Hot Mix Asphalt, 12.5mm	TON	1,500		
403.209	Hot Mix Asphalt, Hand Work	TON	300		
409.15	Bituminous tack coat, applied	GAL	750		
603.15	12" Culvert HDPE Pipe	LF	240		
604.262	4' Diameter Catch Basin Type B5-C	EA	4		
605.09	6" Underdrain Type B	LF	1,200		
606.10	Adjust Existing Mailbox Post	EA	30		
609.11	Vertical Granite Curb	LF	2,400		
609.237	Terminal Curb Type 1- 7'	EA	10		
610.08	Plain Riprap	TON	100		
615.08	Loam, Seed & Mulch	SY	10,000		
620.54	Stabilization/Reinforcement Geotextile	SY	2,200		
659.10	Mobilization	LS	1		
	Total				

Written total amount is: _____

Company Name: _____

Signed by: _____

Title: _____

Print Name: _____

Address: _____

Tel. # _____ Fax # _____

Date: _____

Addendum Acknowledged:

_____ Date _____

_____ Date _____



