



General Notes

1. PROPOSED SIDEWALKS WILL BE 5' WIDE AND ABUT THE GRANITE CURBING. THUS, REMOVING ESPLANADES.
2. TREES AND STUMPS WITHIN THE ESPLANADE AND SIDEWALK AREA ON THE WEST SIDE OF THE STREET WILL BE REMOVED. TREES WILL BE REPLACED WITH (4) 3" RED MAPLE TREES, (3) 1.5" - 2" IVORY SILK LILAC, AND (3) 1.5" - 2" ORNAMENTAL PEAR TREES. LOCATIONS TO BE DETERMINED BY THE CITY.
3. REPLACE ALL GRANITE CURBING TO MATCH EXISTING CURB LINE UNLESS OTHERWISE SPECIFIED.
4. ROADWAY SHALL BE RECONSTRUCTED TO MATCH EXISTING GRADE AND DIMENSIONS UNLESS OTHERWISE SPECIFIED.
5. CARE SHALL BE TAKEN DURING ROAD EXCAVATION DUE TO SHALLOW GAS LINE. DEPTH CHECKS AS LOW AS 28" BELOW TOP OF PAVEMENT.
6. ROADWAY BUILDUP:
 15" - TYPE D GRAVEL
 3" - TYPE A GRAVEL
 2" - 19mm BASE COURSE
 1-1/2" - 9.5mm SURFACE
7. DRIVEWAY BUILDUP:
 12" - TYPE A GRAVEL
 2" - 12.5mm BASE COURSE
 1" - 9.5mm SURFACE
8. SIDEWALK BUILDUP:
 12" - TYPE A GRAVEL
 1" - 9.5mm BASE COURSE
 1" - 9.5mm SURFACE

No.	Revision/Issue	Date

Firm Name and Address

Project Name and Address
 2016 RECONSTRUCTION PROJECT
 HIGHLAND AVENUE
 AUBURN, ME 04210

Project 2016 RECONSTRUCTION PROJECT	Sheet
Date 5/27/2016	01
Scale 1" = 30'	

