

**SUPPLEMENTAL SPECIFICATIONS  
SECTION 619  
MULCH**

The provisions of Section 619 of the Standard Specifications shall apply with the following additions and modifications:

**619.01 Description**

This work shall consist of furnishing and applying mulch to all seeded areas, in accordance with the specifications, plans, and at the direction of the City.

**619.03 General**

An approved wood cellulose fiber compatible with recommended hydro-seeding practices shall be applied as mulch for areas with slopes equal to or greater than 3:1. This mulch shall be applied simultaneously with the seed and shall be of sufficient quantity to protect the seed and hold moisture in to insure a satisfactory growth of grass. The specifications for the wood cellulose fiber proposed for use by the Contractor shall be presented to the Engineer for acceptance at least ten (10) working days prior to the application thereof.

All other areas to receive loam and seed shall receive hay or straw mulch, or wood cellulose fiber, applied in accordance with the Standard Specifications.

**619.06 Method of Measurement**

Mulch will be measured by the surface area in Units of 1000 square feet along the slope of the ground.

**619.07 Basis of Payment**

The accepted quantities of mulching will be paid for at the contract price per unit, which price shall be full compensation for furnishing and spreading mulch, and all labor, materials, and equipment necessary to satisfactorily complete the work.

<b><u>Pay Item</u></b>	Payment will be made under:	<b><u>Pay Unit</u></b>
619.1201	Mulch, Plan Quantity	Unit