

**ADDENDUM NO. 2**  
TO  
CITY OF AUBURN, MAINE  
2026 Spring Street Mill & Fill Project BID#2026-017  
**DATE: 2/13/2026**

*This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on the Bid Form.*

---

**Q: Is the City testing HMA?**

A: No this City will not be providing QA.

**Q: Can the road be closed during milling/paving operations?**

A: No.

**Q: Please provide more information on the catch basin elevations.**

A: The structures should be roughly 6' deep to include a 2' sump with existing inverts at approximately 4' below rim. A "D" top is required to support a granite inlet stone.

**Q: Can the project be started at any point during the season?**

A: The project can begin as early as April 15<sup>th</sup> of this year.

**Q: Does the City want the millings from this project?**

A: The City would accept the millings at the Public Works pit on Gracelawn Road.

**Q: What is the intention for Item #202.06?**

A: Removing pavement for sidewalks and entrances to be rebuilt.

**Q: What is the estimate for this project?**

A: \$625,000.00

**Q: Are there any pre-existing drainage issues?**

A: The Engineering Department is not aware of existing drainage issues along the corridor.

**Q: Is the Contractor cold planning for depth (2")?**

A: Yes, with the slope being a straight grade from centerline to granite curb.

**Q: What is the City's intension for lowering the catch basins?**

A: Lower and plate for the milling operations and bring back to grade level for surface.